

Volume – II

Section – I: Control and Protection

- CHAPTER – 1:** CONTROL AND PROTECTION GENERAL CONSIDERATIONS,
TECHNOLOGY DEVELOPMENT
- CHAPTER – 2:** CONTROL SYSTEM OF HYDRAULIC ELECTRIC STATIONS
- CHAPTER – 3:** ELECTRICAL PROTECTION SYSTEM

Section – II: Auxiliary Systems

- CHAPTER - 4:** ELECTRICAL AUXILIARY SYSTEM
- CHAPTER –5:** MECHANICAL AUXILIARY SYSTEM

Section – III: Step up Substation

- CHAPTER – 6:** GENERATOR TRANSFORMER
- CHAPTER – 7:** HIGH VOLTAGE CIRCUIT BREAKER
- CHAPTER – 8:** SWITCHYARD EQUIPMENT
- CHAPTER – 9:** POWER EVACUATION, MAIN SINGLE LINE DIAGRAM, GRID
INTERCONNECTION AND SWITCHYARD LAYOUT
- CHAPTER – 10:** DESIGN OF EHV AND UHV SUB-STATION

CONTENTS

	TITLE	PAGE NO.
SECTION – I: CONTROL AND PROTECTION		
CHAPTER-1	CONTROL AND PROTECTION GENERAL CONSIDERATIONS, TECHNOLOGY DEVELOPMENT	1
1.1	Control System	1
1.1.1	Standards and Codes	1
1.2	Methods of Control	2
1.3	Major Controllers for Component of Hydro Electric Plant	2
1.3.1	Intake	3
1.3.2	Turbine and Governing System	4
1.3.3	Generator and Excitation System	4
1.3.4	Step up Transformers	4
1.3.5	Generator Breakers	4
1.3.6	Auxiliary Systems	4
1.4	Technology - Control System	4
1.4.1	Conventional Control System	4
1.4.2	Modern Control System	5
1.4.3	Modern Control of Power Station	5
1.5	Protection System	6
1.5.1	General	6
1.5.2	Mechanical Protection System	7
1.5.3	Electrical Protection System	7
1.6	Protective Relay Technology	7
1.7	Considerations for Application of Digital Control and Protection System	8
1.7.1	Digital Control and Protection System	8
1.7.2	Main disadvantages and advantages for application of digital protection in hydroelectric station	8
1.7.3	Modern Indian Practice	10
1.8	Power and Control System Single Line and Schematic and Detailed Wiring Drawings	10
1.8.1	Graphic Symbols	10
1.8.2	Device Numbers	11
1.8.3	Suffix Letter	12
1.8.4	Schematic Diagrams	12
	References	12
CHAPTER-2	CONTROL SYSTEM OF HYDRAULIC ELECTRIC STATIONS	13
2.1	Conventional Control System with Relay Logic (Mechanical/Analogue Electronic Governor)	13
2.1.1	Local Manual (Mechanical or push button) control	13
2.1.2	Local Control of Unit from Unit Control Board (Semi Automatic)	13
2.1.3	Control of Unit from Central Control Room (Automatic Control)	14
2.1.4	Synchronizing	15
2.1.4.1	Manual Synchronizing	15
2.1.4.2	Automatic Synchronizing	15

2.1.4.3	Self Synchronizing	15
2.1.5	Automatic Load Control	16
2.1.5.1	Mechanical Governors	16
2.1.5.2	Analogue Electronic Governors	16
2.1.5.3	Reactive Power Control	16
2.1.6	Machine Running Supervision	16
2.1.6.1	Load Frequency Control	16
2.1.6.2	Reactive Power and Voltage Control	17
2.1.6.3	Supervision of Alarm and Protective equipment	17
2.1.7	Hydraulic Control	17
2.1.8	Large Hydro station – Conventional Control System	17
2.1.8.1	Unit control	18
2.1.8.2	Centralised Control	18
2.1.9	Conventional Automatic Control of Small Hydro Station	23
2.1.10	Semi Automatic Conventional Control of Grid Connected Small Hydro Station with Electronic Governor	27
2.1.10.1	Press “SART” Push Button – Semi Automatic Starting	27
2.1.10.2	Stopping the Units	27
2.2	MODERN CONTROL OF LARGE HYDRO POWER STATIONS - DISTRIBUTED COMPUTER CONTROL SYSTEMS	31
2.2.1	Introduction	31
2.2.2	Functional Capabilities	31
2.2.3	System Architecture, Communication and Databases	33
2.2.3.1	Control Data Networks	33
2.2.3.2	Man-Machine Interface (MMI)	33
2.2.4	Grounding	33
2.2.5	Static Control	34
2.2.6	Control and Monitoring Plant Equipment	34
2.2.7	Supervisory Control and Data Acquisition (SCADA) – Functions	34
2.2.8	Description of a Typical Distributed Control System (Stepped Sequence Starting)	35
2.2.8.1	Functional Group and Drive Control	35
2.2.8.2	Sequence Control	36
2.2.8.3	Modes of Operation	36
2.2.8.4	Automatic Mode	36
2.2.8.5	Step by Step Mode	36
2.2.8.6	Automatic Inactive Mode	36
2.2.8.7	Protection Functions	36
2.2.8.8	Input /Output Modules	46
2.2.8.9	Input/Output Relays	46
2.2.8.10	Processor Modules (DPU-Distributed Processing Unit)	47
2.2.8.11	Diagnostics	47
2.2.8.12	Power Supply	47
2.2.8.13	Meters and Control Switches	47
2.2.8.14	Alarm and Annunciation	48
2.2.9	Common Control Board	48
2.2.10	Engineering Work Station (Programming & Training Console)	48
2.2.11	Battery and Battery Charger	48
2.2.12	UPS System for SCADA	48
2.2.13	Grounding System and Static Control	49
2.2.14	Testing	49
2.2.15	Typical Technical Specification for computer based group control, monitoring, metering, centralized control, offsite control and data acquisition system (SCADA) for (2 X 75 MW) main power house and offsite control for two canal based (2 x 11 MW each) hydro	49

	generating station.	
2.2.15.1	General	49
2.15.2.2	Control Hierarchy	50
2.2.15.3	Functional System and Scope of Work	54
2.2.15.4	Applicable Standard	55
2.2.15.5	Control and Monitoring of Plant Equipment: General Considerations	56
2.2.15.6	Specific Parameters and Layout Conditions	57
2.2.15.7	Rating and Functional Characteristics	59
2.2.15.8	System Architecture, Communication and Databases	61
2.2.15.9	Control, Monitoring and Data Acquisition System Design	62
2.2.15.10	Specification of Main Equipments	66
2.2.15.11	SCADA Functions	70
2.2.15.12	Quality Assurance	72
2.2.15.13	Standardisation	72
2.2.15.14	Factory Assembly and Tests	72
2.2.15.15	Field Test	74
2.2.15.16	Training	74
2.2.15.17	Documents and Drawings	75
2.2.15.18	Communication Links	75
2.3	CONTROL OF SMALL HYDRO STATION – INTEGRATED GOVERNOR AND PLANT CONTROL SYSTEM	76
2.3.1	Introduction	76
2.3.2	Consideration for Selecting Governor and Control System	77
2.3.3	Technology for Economic Small Hydro Control	77
2.3.3.1	General Considerations	77
2.3.3.2	Microprocessor Control	77
2.3.3.3	Integrated Governor and Plant Control System	78
2.3.4	Computer (PLC) based control system for SHP upto 5 MVA	80
2.3.4.1	PLC Based System	80
2.3.5	PC based Integrated Generation Controller	84
2.3.6	Microprocessor based Generation Controllers	86
2.3.6.1	Generation Controller	86
2.3.6.2	PI Dedicated Governor	86
2.3.7	Grid Connection for New and Existing SHP with different type of Governors	88
2.3.8	Typical Examples of Group Control and Interconnection with Grid of Small Hydro with different types of Governors	89
2.3.8.1	Monitoring and Remote Control Computerized System	89
2.3.8.2	Existing Control Equipment	90
2.3.8.3	Revised Control Scheme – Design Criteria	93
2.3.8.4	Hydraulic Control	97
2.3.9	Modern practice for control of small hydro plants (100 kW to 5000 kW)	97
2.4	CONTROL OF MICRO HYDEL	100
2.4.1	Modern Digital Electronic Load Controller for Microhydro	100
2.4.2	Advantage of Electronic Load Controller	100
2.4.3	Governor Functions	100
2.4.3.1	Architectural View and Hardware Details of the Digital Load Controller	101
2.4.4	Detailed Specification	101
2.4.5	Triacs	101
2.4.6	Stability	102
2.4.7	Parallel Operation	102
2.4.8	MicroHydro Standard (AHEC) Recommendations	102

	References	104
CHAPTER – 3	ELECTRICAL PROTECTION SYSTEM	105
3.1	DESIGN CONSIDERATION	105
3.1.1	Reliability of Protection	105
3.1.2	Selectivity	105
3.1.3	Speed	105
3.1.4	Sensitivity	105
3.1.5	Protection Zones	105
3.1.6	Primary and back up Protection	106
3.1.7	Fault Data	106
3.1.8	Fault Current Versus Load Current	107
3.1.9	Circuit-Interrupting Devices	107
3.1.10	Sensing Devices	107
3.1.11	Type of Protective Relays	107
3.1.12	System Studies	108
3.1.13	Required Data	108
3.1.14	Performance of Studies	108
3.2	INSTRUMENT TRANSFORMER	109
3.2.1	Introduction	109
3.2.2	Current Transformer	109
3.2.3	Terminology of Current Transformer (IS: 2705)	110
3.2.4	Application of Protective Current Transformers	111
3.2.5	Special Application (PS class CTs)	113
3.2.6	Protective Voltage transformers	114
3.2.6.1	Terminology	114
3.2.6.2	Limits of Voltage Error & Phase Displacement	114
3.2.6.3	Voltage Transformer Intended to Produce Residual Voltage	115
3.2.6.4	Special Application	115
3.2.6.5	Application of Measuring Voltage Transformers	115
3.2.6.6	Accuracy Class	115
3.2.7	Application of Protective Voltage Transformers	115
3.2.8	Choice of Connection (phase to Phase) (V)	116
3.2.9	Star- Star	116
3.2.10	Star – Broken Delta	116
3.2.11	Voltage and insulation level and overvoltage withstand etc.	116
3.2.12	Typical Example	116
3.3	GENERATOR PROTECTION	118
3.3.1	Introduction	118
3.3.2	Generator, Excitation Systems and Generating Station Arrangements	118
3.3.3	Possible Faults	119
3.3.4	Thermal Protection	121
3.3.5	Generator Stator Fault Protections	121
3.3.6	Generator Grounding and Stator Earth Fault Protection	128
3.3.7	Generator Rotor Earth Fault Protection	132
3.3.7.1	Potentiometer method	132
3.3.7.2	AC Injection Method	132
3.3.7.3	DC Injection Method	133
3.3.7.4	Rotor Earth fault Brushless Excitation System	134
3.3.7.5	Back up Protection	134
3.3.8	Filed Failure	134
3.3.9	Unbalanced Stator Loading Protection	137
3.3.10	Loss of Synchronism	137
3.3.11	Failure of Prime Mover	137

3.3.12	Over Voltage Protection	138
3.3.13	Back up Over Current Protection	138
3.3.14	Numerical Generator Protection relays	138
3.3.14.1	Areva Multifunction Digital Generator Protection Relays	138
3.3.14.2	Woodward Multifunction Digital Generator Protection Relays	140
3.3.14.3	Siemens Multifunction Digital Generator Protection Relays	141
3.3.15	Tripping and Annunciation	141
3.3.16	Protection Schemes	141
3.3.16.1	Small Hydro Generator Protection Scheme	141
3.3.16.2	Typical Protection scheme provided for small hydro by conventional relays	142
3.3.16.3	Typical protection schemes with multifunction numerical generator protection relays	145
3.4	POWER TRANSFORMER PROTECTION	148
3.4.1	Introduction	148
3.4.2	Possible Faults	148
3.4.3	Fault Detection System	149
3.4.3.1	Gas Analysis	149
3.4.4	Factors Affecting Performance of Electrical Protection	149
3.4.5	Protection System for Transformers	149
3.4.6	Overall Unit Differential – Special Relay Protection	153
3.4.7	Over Flux Protection	153
3.4.8	Differential Protection of Auto Transformers	154
3.4.9	Transformer Differential Protection by Numerical Relays	154
3.5	BUS BAR PROTECTION	157
3.5.1	General	157
3.5.2	Metal Clad Bus Bar Installation	157
3.5.3	High Voltage Bus Bars	157
3.5.4	Current Transformer Requirements	159
3.5.5	Typical Schemes	159
3.5.6	Check Features	159
3.5.7	Circuit Supervision	159
3.5.8	Location of Current Transformer	159
3.6	LINE PROTECTION (TRANSMISSION LINE)	160
3.6.1	Introduction	160
3.6.2	General Considerations	160
3.6.2.1	Line Length and power to be transmitted	160
3.6.2.2	Type of Line	162
3.6.2.3	Criticality of Line	162
3.6.2.4	System Factors	162
3.6.2.5	Communication	162
3.6.2.6	Old Versus New Technology	162
3.6.2.7	Redundancy and Back up Consideration	162
3.6.2.8	Reclosing	163
3.6.3	Feeder Protection Scheme for Hydro Stations	163
3.6.4	Over current relays	163
3.6.4.1	Direction Over current Relay	164
3.6.5	Distance Relays	166
3.6.5.1	Distance Schemes	168
3.6.5.2	Step Distance Schemes	170
3.6.6	Power Line Carrier and other Pilot Schemes	171
3.6.6.1	Communication Channels	171
3.6.6.2	Power line carrier communication	171
3.6.6.3	Channel (Pilot) Aided Distance Protection Scheme for high voltage	172

	line for Large Power Station Interconnection	
3.6.7	Numerical Line Protection Relays	173
3.6.7.1	Over-current Relays	173
3.6.7.2	Distance Relays	174
3.6.8	Typical Protection Schemes for Two Terminal Transmission Lines (Interconnection with Grid)	175
3.6.8.1	Typical Protection Schemes for Two Terminal Transmission Lines – 66kV to 220 kV (Interconnection with Grid of Large Hydro)	175
3.6.8.2	Typical Protection Schemes for Two Terminal Sub Transmission Lines (Interconnection with Grid of Small Hydro)	176
3.6.8.3	Typical Protection Schemes for Interconnection with Grid of Micro Hydro	177
3.7	RELAYING FOR E.H.V. SYSTEM (420 kV and above)	179
3.7.1	Introduction	179
3.7.2	Description of 420 kV System	180
3.7.3	Design Consideration	180
3.7.3.1	Fault Currents	180
3.7.3.2	Transient Stability	181
3.7.3.3	Substation Bus Arrangement	184
3.7.3.4	Protective Relay Design	184
3.7.4	Transmission Line Protection	185
3.7.4.1	Main I (Primary) Protection	185
3.7.4.2	Second Main Protection	186
3.7.4.3	Back-up Protection	187
3.7.5	420 kV Bus Bar Protection	187
3.7.6	Protection of 420 kV Transformer	187
3.7.7	Circuit Breaker Failure Relaying (Local Breaker back-up Protection)	187
3.7.8	Auto-Reclosing 420 kV Line	189
3.7.9	Other Relaying	190
3.7.10	Conclusion	191
3.7.11	Numerical Digital Line relays	191
3.8	SPECIFICATIONS FOR PROTECTION SYSTEM FOR LARGE HYDRO STATIONS	192
3.8.1	General	192
3.8.2	Multifunction Digital Protection Relay	193
3.8.3	Generator, Generator Transformer and Auxiliary Transformer Protection	194
3.8.3.1	Generator Differential Protection	194
3.8.3.2	Generator Transformer Differential Protection	194
3.8.3.3	Link Line Differential Protection	194
3.8.3.4	Generator Ground Fault Protection	194
3.8.3.5	Gen. Transformer HV restricted earth fault protection	194
3.8.3.6	Generator Over-Voltage Protection	194
3.8.3.7	Unit Auxiliary Transformer Protection	195
3.8.3.8	Negative Phase Sequence Current Protection (Generator)	195
3.8.3.9	Generator Field Failure Protection	195
3.8.3.10	Standby Earth Protection	195
3.8.3.11	Generator Over speed Protection	195
3.8.3.12	Generator Rotor Earth – Fault Protection	195
3.8.3.13	Potential Transformer Fuse Failure Protection	196
3.8.4	245 kV Bus-Bar Protection	196
3.8.5	220/132/11 kV, 40/36/4 MVA Transformer Protection	196
3.8.6	245 kV Feeder Protection	196
3.8.7	245 kV Bus Coupler Protection	197
3.8.8	245 kV/420 kV interlinking transformer protection	197

3.8.9	420 kV Line Protection_(280 km long line)	197
3.8.10	Auto-Reclose Relaying for 245 kV Lines, Bus Coupler and 420 kV Line	198
3.8.11	420 kV Bus – Bar Protection	199
3.8.12	Circuit Breaker Faults Protection	199
3.8.13	132 kV Feeder Protection	199
3.9	TYPICAL TECHNICAL SPECIFICATION OF SMALL HYDRO PROTECTION SYSTEM OF 2 x 2 MW WITH MANUAL BACKUP	199
3.9.1	General	199
3.9.1.1	Metering	199
3.9.1.2	Protection Relays	199
3.9.1.3	Protection	200
3.9.1.4	Protection and Metering Details	200
3.9.2	Generator	203
3.9.3	Transformer	203
3.9.4	33 kV Line Protection	204
	References	205

SECTION – II: AUXILIARY SYSTEMS

CHAPTER – 4	ELECTRICAL AUXILIARY SYSTEMS	207
4.1	Electrical Auxiliaries System Equipment - General Requirement	207
4.1.1	Electrical Supplies for Auxiliary Equipment	207
4.1.2	High Voltage Switchgear	207
4.1.3	Electric Motors	208
4.1.4	Starters and Contactors	209
4.1.5	Moulded Case Circuit Breakers	210
4.1.6	Control Relays	210
4.1.7	Terminal Blocks	210
4.1.8	Equipment Wiring	210
4.1.9	Cubicles and Control Panels	211
4.1.10	Earthing	211
4.1.11	Labels and Plates	211
4.1.12	Warning Labels	212
4.1.13	Labels For Cables	212
4.1.14	Single-Line Diagrams	212
4.1.15	Key System For Electric Boards	212
4.1.16	Instrumentation and Control Equipment	212
4.2	AUXILIARY POWER SUPPLY SYSTEM	214
4.2.1	Auxiliary Electrical Equipment	215
4.2.2	Requirement for Auxiliary Power Supply	216
4.2.3	Auxiliary Power Supply Systems	216
4.2.4	Auxiliaries Control	218
4.2.5	Auxiliary Power Supply for Large/Mega Power Stations	218
4.2.6	Auxiliary power supply for Medium Size Hydro Power Station above 5 MW	219
4.2.7	Auxiliary power supply for Smal Hydro Power Station below 5 MW	219
4.2.8	Auxiliary Power Supply for Micro Hydro	224
4.2.9	Auxiliary Transformers	224
4.3	DIRECT CURRENT (D.C.) AUXILIARY POWER SYSTEM	225
4.3.1	General	225
4.3.2	D. C. Batteries	225
4.3.3	Battery Room	226

4.3.4	Battery Voltage and Number of Cells	226
4.3.5	Battery Accessory	228
4.3.6	Ampere Hour Capacity of DC Batteries	228
4.3.7	Battery Charging Equipment	231
4.3.8	Switching from Float to Equalizing Mode	231
4.3.9	Construction Features	231
4.3.10	DC System Design	232
4.3.11	DC Switchgear	232
4.3.12	Battery testing	232
4.3.13	DC Power Supply System	232
4.4	UNINTERRUPTIBLE POWER SUPPLY SYSTEM (UPS)	233
4.4.1	UPS System Design	234
4.5	LIGHTING SYSTEM	235
4.5.1	General Requirements	235
4.5.2	Standards	235
4.5.3	General Requirements	235
4.5.3.1	Design Criteria	235
4.5.4	Emergency Supply	237
4.5.5	DC System Design	237
4.6	POWER AND CONTROL CABLES AND CABLING	238
4.6.1	Power and Control Cables	238
4.6.2	Duty Requirements/Design Criteria	239
4.6.3	Range Of Cables	240
4.6.4	Co-Axial Cable	241
4.6.5	Cabling	242
4.7	GROUNDING SYSTEM FOR GENERATING STATIONS AND STEP UP SUB STATIONS	244
4.7.1	Introduction	244
4.7.2	Standards, Codes and Rules – (Latest Amended)	244
4.7.3	Design Objectives	244
4.7.4	Parameters to be considered for designing Earthing System	245
4.7.4.1	Site Soil Resistivity Measurements and Installation	245
4.7.4.2	Effect of moisture, salts and Temperature	245
4.7.4.3	Magnitude of Fault Current	245
4.7.4.4	Material and Size of Conductor	246
4.7.5	Station Ground Resistance	246
4.7.6	Grounding System for powerhouse & Sub Station	247
4.7.6.1	Current Carrying Capacity	247
4.7.6.2	Control of Ground Potentials and Gradients	248
4.7.6.3	Maximum Touch and Step Potential	248
4.7.6.4	Maximum Value of Station Voltage Rise (Transfer Potential) and Station Ground Resistance	249
4.7.6.5	Ground Resistance of Powerhouse and Substation	249
4.7.6.6	Maximum Ground Fault Current	249
4.7.6.7	Mechanical Reliability	250
4.7.6.8	Electrical Reliability	250
4.7.6.9	Resistance to Corrosion	250
4.7.6.10	Low Impedance for System Operation	250
4.7.6.11	Provision for test and Inspection	250
4.7.6.12	Grounding Material	250
4.7.7	Generating Station Grounding Design of Powerhouse and Substation	251
4.7.7.1	Design Procedure	251
4.7.7.2	Generating Station Ground Grid Design	252
4.7.7.3	Site Soil Resistivity	252
4.7.7.4	Ground fault Current	252

4.7.7.5	Magnitude of fault Currents and Grid Current at Hydro Station	253
4.7.8	Design of Grounding Systems for Micro Hydro and Medium Voltage Station	254
4.7.9	Grounding system design for SHP up to 5 MW and connected to grid at 33 kV and below and earth resistivity up to 100 ohm meter	256
4.7.9.1	Earthing Practice of Sub Station	256
4.7.9.2	Allowable values of resistance of grounding system	260
4.7.9.3	Earthmat Under Generating Station	260
4.7.9.4	Typical Examples	260
4.7.10	Grounding System SHP Above 5 MW or Interconnected with grid at 66 kV and above	263
4.7.10.1	Mukerian SHP (2 x 9 MW)	263
4.7.11	Earthing Electronic Equipment	265
4.7.12	Installation	265
4.7.13	Typical Technical Specifications for Grounding System	267
<u>Annexure-4.7.7.1</u>	SOIL RESISTIVITY MEASUREMENTS	268
<u>Annexure-4.7.7.2</u>	INSTALLATION OF GROUNDING SYSTEM	273
4.8	COMMUNICATION SYSTEM	283
4.8.1	General	283
4.8.2	Voice Communication System	283
4.8.3	Dedicated Communication System	283
4.8.3.1	Power line carrier communication	283
4.8.3.2	Fibre optic cable	285
4.8.3.3	Microwave communication system	286
4.8.3.4	Radio Communication System	286
4.8.4	Typical specifications	286
4.8.4.1	Communication Link	286
4.8.4.2	Dedicated Communication by Fiber Optic System Cable	287
4.8.4.3	Fiber optic cable	287
4.8.4.4	Repeaters	287
4.8.4.5	Local area network (LAN)	287
4.8.4.6	PLCC System	287
	<u>References</u>	288
CHAPTER-5	MECHANICAL AUXILIARIES SYSTEM	289
5.1	Mechanical Auxiliary System Equipment General Requirement	289
5.2	E.O.T. CRANE	291
5.2.1	Typical EOT Cranes Specifications	291
5.3	COOLING WATER SYSTEM	293
5.3.1	Water Requirements	293
5.3.2	Sources	293
5.3.3	Head requirements	294
5.3.4	Treatment	294
5.3.5	Pumps	294
5.3.6	Piping	294
5.3.7	Typical Cooling Water Systems Specification	295
5.4	DEWATERING AND DRAINAGE SYSTEM	295
5.4.1	General	295
5.4.2	Dewatering System	296
5.4.3	Drainage System	296
5.4.4	Typical Drainage and Dewatering Systems Specification	297
5.5	COMPRESSED AIR SYSTEM	298
5.5.1	Brake Air System	298
5.5.2	Governor Air System	299

5.3.3	Depressing Water in Turbine Casing	299
5.3.4	Service Air System	299
5.5.4	Typical Compressed Air System Specification	300
5.6	FIRE PROTECTION SYSTEM	302
5.6.1	General	302
5.6.2	Codes & Standard	302
5.6.3	General Consideration for Design of Fire protection System	302
5.6.4	Fire Fighting System in Generating Station	303
5.6.5	Fire Prevention	303
5.6.6	Fire Detection and Annunciation	304
5.6.7	Fire Extinguishing	304
5.6.8	Hydrant System	304
5.6.9	High Velocity Water (HVW) Spray System	305
5.6.10	Water Supplies	306
5.6.11	Portable and mobile Fire Extinguishing	306
5.6.12	Instrumentation and Control	307
5.6.13	Fire Fighting System	308
5.6.14	Fire Detections	309
5.6.15	Fire protection Scheme Recommended	310
5.6.16	Fire Protection System Typical Specification	310
5.7	VENTILATION AND AIR CONDITIONING SYSTEM	312
5.7.1	General	312
5.7.2	Types of Ventilation	313
5.7.3	General Rules For Design	313
5.7.4	Fans	314
5.7.5	Air Intake And Exhaust -Openings	314
5.7.6	Air Cleaning	315
5.7.7	Air-Conditioning	315
5.7.8	Ducts	316
5.7.9	Air Distribution Control	316
5.7.10	Air Conditioning and Ventilation System Recommended	316
5.8	WATER LEVEL SENSING	316
5.8.1	Water Level Sensing specification	316
5.9	OIL SYSTEM	317
5.9.1	Typical specifications	318
	<u>References</u>	319

SECTION – III: STEP UP SUBSTATION

CHAPTER-6	GENERATOR TRANSFORMER AND INSULATION COORDINATION	321
6.1	General	321
6.1.1	Relevant national and international standards	321
6.2	Generator Transformers	321
6.3	Transformer Rating	321
6.4	Cooling	322
6.5	Temperature Rise, Overload Capacity and Continuous Rating	323
6.6	Electrical Characteristics	323
6.6.1	Type of Transformer and Operating Conditions	323
6.6.2	Continuous Maximum Rating and Overloads	323
6.6.3	Voltage Ratio	323
6.6.4	Duty Under fault Condition	323
6.6.5	Electrical Connections	324
6.6.6	Flux density	324

6.6.7	Current Density	324
6.6.8	Short Circuit Strength	324
6.6.9	Frequency and System Voltage	324
6.6.10	Parallel Operation	324
6.6.11	Vibration and Noise	325
6.7	Basic Insulation Level and Insulation Co-ordination upto 220 kV System	325
6.7.1	Over-voltages	325
6.7.2	Selection of basic Impulse Insulation Level (BIL) upto 220 kV System	325
6.7.3	Station Design for Lightning and Standardisation of Insulation Levels	325
6.7.4	Existing Insulation Practice of Substation Equipments	327
6.7.5	Protection with Spark Gaps	328
6.8	Impedance	329
6.9	Terminal Bushings	329
6.10	Transformer Efficiency	330
6.11	Tanks	330
6.12	Pressure Relief Device	331
6.13	Anti Earthquake Clamping Device	331
6.14	Dielectric Tests	331
6.15	Oil Conservator System and Accessories	331
6.16	Oil Containment and Fire Protection System	331
6.17	Transformers for Small Hydro	331
6.18	Generator Transformers for Large Hydro upto 245 kV	332
6.19	Equipment Insulation and Coordination of EHV System	332
6.19.1	Over-Voltages in EHV Overhead Lines	333
6.19.2	Dehar EHV System over Voltages	337
6.19.3	Lightning Arrestor	339
6.19.4	Transformer Insulation Level	340
6.19.5	Insulation Level of other Switchyard Equipment	342
6.19.6	Conclusions	342
6.19.7	Present practice (CBI & P) for 420 kV class generator transformer	342
6.20	420 kV Class Generator Transformer	342
6.21	Factory and Field Testing for Large Transformers	343
6.21.1	Routine Test	343
6.21.2	Type Tests	343
6.21.3	Special Tests	343
6.21.4	Additional tests	343
6.21.5	Recommended field tests	344
	REFERENCES	344
	Annexure – 6.1	346
	Example Calculation for Rationalization of capitalization Formula for Transformer Losses	
	Annexure- 6.2	348
	Typical Technical Specification: Large Generator Transformers	
CHAPTER-7	HIGH VOLTAGE CIRCUIT BREAKER	367
7.1	Introduction	367
7.1.1	Standards	367
7.2	Type of HV Circuit Breakers	367
7.2.1	Sulphar Hexafluoride as an Arc Quenching Agent	367
7.2.2	Vacuum Circuit Breaker	368
7.3	Advantages and Disadvantages	369

7.3.1	Evaluation of SF6 and Vacuum Switching Technologies	369
7.3.2	Protection Classes for Switchgear Installation	370
7.4	Rated Characteristics	371
7.4.1	Rated Voltage	371
7.4.2	Rated Insulation Level	372
7.4.3	Rated Frequency	373
7.4.4	Rated Normal Current	373
7.4.5	Rated short-time withstand current	373
7.4.6	Rated Short Circuit Breaking Current	373
7.4.7	Rated Short Circuit Making Current	374
7.4.8	Transient Recovery Voltage and Restriking Voltage and First Pole to clear Factor	374
7.4.8.1	Rated Transient Recovery Voltage (TRV) for terminal faults	374
7.4.8.2	First Pole to Clear Factors	374
7.4.8.3	Recovery voltage	375
7.4.10	Rated Characteristics for Short-Line faults	375
7.4.11	Rated Supply Circuit characteristics	376
7.4.12	Rated line Characteristics	376
7.4.13	Rated out –of-phase breaking current	376
7.4.14	Rated Line Charging Breaking Current	376
7.4.15	Rated time quantities and operating sequence	377
7.5	Co-ordination of rated values	378
7.6	Tests	379
7.6.1	Type Test	379
7.6.2	Routine tests	379
7.7	Fault Calculation	379
7.7.1	Staged Short Circuit Tests	380
7.7.2	Circuit Breaker Rating for Short Circuit Duty	380
7.7.3	Simplified Methods for calculation short circuit current	380
7.7.4	E/X Simplified method as per IEEE std. C37010-1999	381
7.7.5	Simplified Method	381
7.8	Specification	381
	Annexure -1	384
	Typical Example for Calculating Rating Of Circuit Breaker	
	Annexure -2	387
	Technical Specification For SF6 Gas Filled Circuit Breakers	
CHAPTER-8	SWITCHYARD EQUIPMENT- HV Bus Bars, Switchyard Structures, Isolating Switches, Current Transformers, Voltage Transformers, Lightning Arresters	397
8.1	Introduction	397
8.1.1	Standards and Codes	397
8.2	General Requirements	397
8.2.1	General	397
8.2.2	Seismic Consideration	397
8.2.3	Basic Insulation Level and Insulation Coordination	398
8.2.4	Insulators	398
8.2.4.1	Insulator Type	398
8.3	Switchyard Structures	398
8.3.1	Design Data for Design of Switchyard Structures	399
8.3.2	Working Stresses	400
8.3.3	Factor of Safety	400
8.3.4	Slenderness Ratio (L/R)	400
8.3.5	Minimum Thickness for Steel Members	400

8.4	Bus bars	400
8.4.1	Bus bar Material	401
8.5	Isolating Switches and Earthing Switches	401
8.5.1	Temperature Rise	402
8.5.2	Rating	402
8.5.3	Isolator Insulation	402
8.5.4	Arcing Horn & Arcing Contacts	403
8.5.5	Load Break Switches	403
8.5.6	Terminal Connectors	403
8.5.7	Interlocks	403
8.5.8	Supporting Structures	404
8.5.9	Tests	404
8.6	Current Transformers	404
8.6.1	Type and Rating	405
8.6.2	Details of Current Transformer	405
8.6.2.1	Temperature Rise	405
8.6.3	General Requirements of Current Transformer	406
8.6.4	Terminal Connectors 72.5 kV and Above	406
8.6.5	Type of Mounting	406
8.6.6	Tests	407
8.6.7	External Insulation (72.5 kV & Above)	407
8.6.8	Fittings and Accessories (72.5 kV & Above)	407
8.7	Potential Transformer and Coupling Voltage Transformer	407
8.7.1	Type and Rating of Potential Transformer (PT)	408
8.7.2	Temperature Rise	408
8.7.3	12 kV Voltage Transformer	409
8.7.4	Coupling Voltage Transformer (72.5 kV & Above)	409
8.8	Transformers	409
8.9	Lightning Arrestors	410
8.9.1	General Technical Requirements	410
8.9.2	Lightning Protection	411
8.10	Equipment for Communication, Relaying and Tele Metering and Off-site Control	412
8.11	Reactive Compensation Equipment	412
	<u>References</u>	412
CHAPTER – 9	POWER EVACUATION, MAIN SINGLE LINE DIAGRAM, GRID INTERCONNECTION AND SWITCHYARD LAYOUT UPTO 245 kV	413
9.1	General	413
9.2	Grid Connection, Power Evacuation and Switching Schemes	414
9.2.1	Power evacuation in large hydro power stations	414
9.2.2	Grid Connected Small Hydro Power Stations (including microhydro)	414
9.2.3	Generating Station Arrangement	414
9.2.4	Unit Switching Schemes	414
9.2.4.1	Unit Switching Arrangements	414
9.2.5	Switching Schemes for Outdoor Step-up Sub Station	416
9.2.5.1	General Consideration for the Selection of Switching Scheme	416
9.2.6	Switching Schemes for Large Step up Sub-Station	416
9.2.6.1	Double bus single breaker scheme	416
9.2.6.2	Single Bus Schemes	417
9.2.6.3	Single Sectionalized Bus	418
9.2.6.4	Other Switching Schemes	419
9.3	Switchyard Layout	420

9.3.1	General	420
9.3.2	Selection of Site	420
9.3.3	Switchyard Equipment	420
9.3.3.1	Generator Transformer	420
9.3.3.2	Circuit Breakers	420
9.3.3.3	Isolators	420
9.3.3.4	Instrument Transformers	421
9.3.3.5	Reactive Compensation Equipment	421
9.4	Electrical and Safety Clearances	421
9.4.1	Electrical Clearances for Installing Equipment in the Field (upto 245 kV)	421
9.4.1.1	Co-relation between insulation Level and minimum Phase to earth Clearances	421
9.4.1.2	Working Safety Clearances	422
9.4.1.3	Minimum and Safety clearances recommended by Central Board of Irrigation and Power manual	422
9.4.1.4	Section Clearances	423
9.4.1.5	Standard Bay Widths (in meters) as per TNEB Practices	424
9.5	GIS Sub Station	424
9.5.1	Gas Insulated Switchgear (GIS)	424
9.5.2	Details of GIS Substation as per CBI &P Manual on Substation Layout - 2006	425
9.5.2.1	Supporting Structures	425
9.5.2.2	Grounding	426
9.5.2.3	GIS Terminations	426
9.5.3	Metal Clad GIS Switchgear	426
9.6	Switchyard Layout	427
9.6.1	Switchyard Layout for Small hydro and large hydro up to 245 kV	427
	<u>References</u>	427
CHAPTER-10	DESIGN OF EHV AND UHV SUB-STATION	437
10.1	Introduction	437
10.2	Switching Schemes For EHV Substations	437
10.2.1	Types of Substations	437
10.2.2	Criteria for the selection	437
10.2.3	Discussion for Selection of Bus Scheme for Dehar Step-up Substation	439
10.2.4	Switching Station	445
10.2.5	Single Line Diagram	446
10.3	Electrical Clearances For Installing EHV/UHV Equipment in Field	446
10.3.1	Minimum Phase to Ground Clearances	447
10.3.2	Minimum Phase to Ground Clearances for various Insulation Levels	447
10.3.3	Phase-to-Ground Clearances for Dehar Sub-station	449
10.4	Safety Clearances	449
10.4.1	Height of bus bars above ground within sub-station premises	450
10.4.2	Conductor clearance from roadways within sub-station premises	450
10.5	Phase to Phase Clearances	450
10.5.1	Insulation levels	450
10.5.2	Phase to Phase Air Clearances	451
10.6	Electrical clearances for installing EHV/UHV equipment as per CBI & P Recommendations	451
10.7	Layout of Equipment in The Sub-Station	452
10.8	Shielding of Control Cables	452
	<u>REFERENCE</u>	453

